LUMINAIRE SCHEDULE											
FIXTURE TYPE	IMAGE	PRODUCT DESCRIPTION	BASIS OF DESIGN MANUFACTURER	SIZE	INPUT WATTS	LAMP SOURCE (Type, CCT, Delivered Lumens)	DRIVER / BALLAST (Integral/Remote) (Electronic/Magn.) (Dimming Type)	INPUT VOLTAGE	FINISH	MOUNTING	NOTES
F1		2x4 RECESSED LED VOLUMETRIC IN OFFICES ON LEVEL 1	FINELITE HPR-LED-ANR-2x4-DCO-S -935-277V-SC-XX	2 Ft W x 4 Ft L x 4" D	27 W	LED 3500K 3680 LM >90 CRI	INTEGRAL ELECTRONIC 0-10V DIM TO 5%	277	AS PER ARCHITECT	RECESSED ACT CLG.	
F2	N	8-FT DIRECT / INDIRECT LINEAR PENDANT ON WOOD BEAMS	FINELITE HP-2-WM-ID-8-B-B-9-35-F F-277V-MB-DC	4" H x 3" D x LENGTH AS SHOWN	12W / LF	LED 3500K 1360 LM/ LF >90CRI	INTEGRAL ELECTRONIC 0-10V DIM TO 5%	277	AS PER ARCHITECT	MOUNTING BRACKET	DUAL CIRCUIT RUNS OF (6) 8 FT PER BEAM (24T PER OVERALL RUN) OUTER 8' INDIRECT PORTION ON BOTH SIDES OF BEAMS TO BE ON 'C' LEG.
F3		4" SQ. RECESSED LED DOWNLIGHT IN BATHROOMS	CALCULITE C4X4L10-DL-35K-CL-XX-XX C4X4L10-N-2-LD-XX	4.5" SQ. x 4.5" H	20 W	LED 3500K 880 LM >90 CRI	INTEGRAL ELECTRONIC 0-10V DIM TO 10%	277	AS PER ARCHITECT	RECESSED GYP. CLG	CONFIRM QUANTITY OF F3s ON MICROINVERTER BEFORE ORDERING
F4	No findage street	4-FT DIRECT / INDIRECT LINEAR PENDANT IN OFFICES	FINELITE S16 LED ID-DCO-4-3E-B-B -935-OPEN-277V-SC-FA-FE-C4	8" W x 2" D x 4 FT L	12 W / LF	LED 3500K 1260 LM / Ft >90 CRI	INTEGRAL ELECTRONIC 0-10V DIM TO 5%	277	AS PER ARCHITECT	AIRCRAFT CABLE PENDANT IN GYP. CLG	
F5		4" SQ. LOW PROFILE LED DOWNLIGHT IN STORAGE / BOH	PHILIPS SLIMLINE S4S-8-35K-7-XX-Z1OU	4" SQ. x	10W	LED 3500K 650 LM	INTEGRAL ELECTRONIC 0-10V	277	AS PER ARCHITECT	SURFACE MOUNT GYP CEILING	
F6		RECESSED LED STEPLIGHT IN CIRCULATION	WAC LIGHTING WL-LED200F-C-WT	3"W x 5"H x 1.5" D	4W	LED 3000K 120 LM	INTEGRAL ELECTRONIC 0-10V	277	WHITE	WALL RECESSED	MOUNT MIN. 12" ABOVE TREAD SEE ARCH DWGS FOR SPACING.
F7		SUSPENDED LED DRUM PENDANT IN STAIRWELL	LUMETTA P2034	14" D x 34" DIA. X SUSP. HT.	57W	LED 3500K 6300 LM >90CRI	INTEGRAL ELECTRONIC 0-10V DIM TO 5%	277	SHADE AS PER ARCHITECT	SLOPED CANOPY / CABLE	PROVIDE 6" DIA. SWIVEL STEM CANOPY
F8	1	WALL MOUNT LINEAR INDIRECT LED IN KITCHENETTE	FINELITE HP2 WM-I	2.25" W x 4" D x 4'-0" L	18.5 W	LED 3500K 880 LM >90 CRI	INTEGRAL ELECTRONIC 0-10V	277	AS PER ARCHITECT	WALL MOUNT	
F9		UNDERCABINET LED STRIP IN KITCHENETTE	CSL LIGHTING ECO-LIGHTBAR LED	1FT & 2FT VERSIONS	6W / LF	LED 3000K 500 LM / LF > 90 CRI	REMOTE ELECTRONIC 0-10V	24DC / 277AC	SATIN ALUMINUM	SURFACE MOUNT CASEWORK	COORDINATE LOCATION OF REMOTE POWER SUPPLY AND LINK TOGETHER
F10	700	NOT USED									
F11	0.35° medium trosted fero	LED TAPE IN CHANNEL AT DESK BEHIND ACRYLIC PANEL	LUMINII TAPE: LL18-35L-XX-XX-XX CHANNEL: SL7-XX-M-SA SUPPLY: PSV-XX-24V-U2DIM-D	LEGNTH AS SHOWN	1.5 W/LF	LED 3500K 125 LM/LF >90 CRI	INTEGRAL ELECTRONIC 0-10V DIM TO 10%	24DC / 277AC	SILVER ANODIZED	UNDER DESKTOP BEHIND ACRYLIC PANEL	COORDINATE LOCATION OF REMOTE POWER SUPPLY WITH ARCHITECT PRIOR TO INSTALLATION.
S 1		LED WALL PACK AT MIDDLE LANDING OF EXTERIOR STAIRS	LITHONIA WST-LED VF	8.5" H x 10" D x 17" L	12 W	LED 3500K 1500 LM	INTEGRAL ELECTRONIC 0-10V	277	AS PER ARCHITECT	WALL SURFACE	
S 2	NO PHOTO	EXISTING SURFACE MOUNTED ENTRY LIGHT AT EXTERIOR SOFFITS	N/A	N/A	18W	VERIFY IN FIELD	VERIFY IN FIELD	277	EXISTING	EXTERIOR SOFFIT	CONTRACTOR TO CONFIRM EXISTING LIGHTING FOR EM EGRESS - REFURBISH MAY BE DESIRED BY ARCHITECT
S 3	NO PHOTO	EXISTING WALL PACK AT TOP LANDINGS OF EXTERIOR STAIR	N/A	N/A	18W	VERIFY IN FIELD	VERIFY IN FIELD	277	EXISTING	WALL SURFACE	CONTRACTOR TO CONFIRM EXISTING LIGHTING FOR EM EGRESS - REFURBISH MAY BE DESIRED BY ARCHITECT
x	EXIT HOOK EXITS	EXIT SIGN AS PER LIFE SAFETY DIAGRAM	LITHONIA EDG-EDGR	11" H x 5.5" D x 13.5" L	5W	LED 3500K	INTEGRAL ELECTRONIC 0-10V	277	AS PER ARCHITECT	RECESSED OR SURFACE WALL / CEILING	CONTRACTOR TO COORDINATE NUMBER OF FACES, MOUNTING, AND ARROW DIRECTIONS PRIOR TO INSTALLATION

ARCHITECT brick. 1266 66th street emeryville, ca 94608 510.516.0167 www.brick-llp.com

CLIENT
marin community college district
835 college avenue
kentfield, ca 94904



- 3/10/17 100% CD/BID SET

PROFESSIONALE PR

college of marin indian valley campus bldg. 11 renovation

novato, california project number: 17-1095

scale: **NONE** date: 16/02/2017

LUMINAIRE SCHEDULE -ELECTRICAL